FE 24 WIRE DRAG

Diagrams 1220-2 & 1222-4

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

DESCRIPTIVE REPORT

Type of Survey .. Wire Drag Field No. R/H-20-8-9-83 Registery No. FE-248WD

LOCALITY

State Virginia

General Locality Atlantic Ocean Sublocality 26 Miles East of Assateague ... Island & Approaches to

Chesapeake Bay

19 83

CHIEF OF PARTY LCDR R.C. Arnold

LIBRARY & ARCHIVES

DATE December 19, 1983

☆U.S. GOV. PRINTING OFFICE: 1985-566-054

- to sign off see Record of application

DAA FORM 77-28 U.S. DEPARTMENT OF COMMERCE	Tavalezza va
1-72) NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	RIEGISTER NO.
HYDROGRAPHIC TITLE SHEET	FE-248WD
INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form,	FIELD NO.
filled in as completely as possible, when the sheet is forwarded to the Office.	RH-20-08-83/RH-20-09-83
State VIRGINIA	
General locality VIRGINIA COAST Atlantic Ocean	
26 Miles East of Assoteague Island and Approaches to Locality "MARINE ELECTRIC", VIRGINIA BEACH	Chasepeake Bay
Scale 1:20,000 Date of surv	June 9 through June 21, 1983 6 JUNE 1983
Instructions dated 6 JUNE 1983 Project No.	
Vessel NOAA SHIPS RUDE (9040) AND HECK (9140)	
Chief of party LCDR RUSSELL C. ARNOLD	
Surveyed by LCDR R. ARNOLD, LCDR D. WINTER, LT N. MILLE	TT, LT E. CLARK, ENS T. CALLAH
Soundings taken by echo sounders hand head; polo RAYTHEON DE-71	9B, Wire Drag, & Preumo fathometer
Graphic record scaled by	
raphic record checked by	
Protracted by Automat	ed plot by
	n : 11
Verification by Evaluation and Analysis Group, Atlantic 11	larine (enter
Verification by Evaluation and Analysis Group, Atlantic M. Soundings in factors feet at MLW SOUNDINGS R	EDUCED FOR PREDICTED TIDES
Verification by Evaluation and Analysis Group, Atlantic II Soundings in fathoms feet at MLW MILLY SOUNDINGS R	EDUCED FOR PREDICTED TIDES
Verification by Evaluation and Analysis Group, Otlantic M. Soundings in fathoms feet at MLW MILL SOUNDINGS R. REMARKS: ALL TIMES RECORDED FOR THIS SURVEY ARE GMT	EDUCED FOR PREDICTED TIDES

Awois and SURF - Rus 4/85

CONTENTS

- A. AUTHORITY
- B. CHARACTER AND LIMITS OF WORK
- C. CONTROL
- D. DATES OF SURVEY
- E. INCOMPLETE ITEMS
- F. EQUIPMENT AND TECHNIQUES
- G. CHARTING RECOMMENDATIONS

DESCRIPTIVE REPORT

To Accompany

WIRE DRAG SURVEY Field Examination 248WD

Field Numbers RH-20-08-83 RH-20-09-83

141 00

A. AUTHORITY

This survey was accomplished in accordance with project instructions for OPR-D670-RU/HE-83, Chesapeake Bay Entrance, Virginia.

B. CHARACTER AND LIMITS OF WORK

The purpose of this portion of OPR-D670 was to investigate the wreck of the collier S/S MARINE ELECTRIC, which sank in February 1983, off Chincoteague, Virginia, and to investigate an obstruction charted near the "CB" Buoy in the outbound lane of the separation scheme at the southern entrance to Chesapeake. Bay.

C. CONTROL See the Evaluation Report, Sections 2. and 6.

Vessel positioning for all work at the MARINE ELECTRIC was accomplished with the ARGO medium range positioning systems operating in the range/range mode at a frequency of 1646.7 KHz. Daily calibrations were performed by circling Chesapeake Bay Entrance Light. Results of daily calibrations and a signal list are the corrected contained in the Supplemental Data File. Frequent whole-lane checks were taken to this report at the "WR" Buoy near the MARINE ELECTRIC. These checks indicated that the HECK lost 1-lane while enroute from Chesapeake Light to the "WR" Buoy. Other than this one loss, the ARGO system functioned well.

Vessel positioning for the "CB" Buoy work was accomplished with the Del Norte

520 short range system. All components of this system were baseline calibrated prior to the start of work. Daily go/no go calibration checks were accomplished by three-point sextant fix with check-fix. All calibration data is contained in the Supplemental Data File.

D. DATES OF SURVEY

This survey was begun on X June 1983 and completed on X June 1983.

E. INCOMPLETE ITEMS

The "Seabed Texturing" portion of this project will be accomplished by the ships in July 1983.

F. EQUIPMENT AND TECHNIQUES See the Evaluation Report

The MARINE ELECTRIC was first investigated with Klein Side Scan Sonar, using a 100 KHz fish, to confirm position and approximate orientation. The wreck was examined by running a box-type pattern around it, with two sides of the box being parallel to the approximate axis (0460-2260) and two sides being approximately perpendicular to the axis (See Appendix B). A fathometer search was then conducted over the suspected high point and a solid trace was obtained that reduced

to 66½ feet (reduced for predicted tide and draft only; no other corrections applied). See fix #148, Sounding Volume 1, JD165. Next, a wire drag was run, parallel to the axis of wreck, which resulted in a hang at an effective depth of 65½ feet. The wreck was subsequently cleared to an effective depth of 65½ feet in one direction and 64½ feet in the opposite direction when the drag was reversed. — Note: any whole feet are used, therefore the hang depth is 65 H, and the clearest depth is 64 feet.

First glance at the wreck on side scan records would seem to indicate that the wreck is in two pieces. However, when scale is applied to the sonargram, the apparent void between the two pieces is needed to account for the total length of the vessel. This fact would thus indicate that perhaps the vessel is still in one piece.

Divers were not utilized primarily due to a large number of sharks that could be seen swimming on the surface near the wreck.

The obstruction at the "CB" Buoy was hung from two directions and investigated by divers to determine least depth. The least depth was rejected as it significantly
conflicted with the wire drag hang data.

G. CHARTING RECOMMENDATIONS

Chart a dangerous wreck cleared by wire drag to an effective depth, reduced for predicted tides, of 6% feet at Latitude 37°52'54.%"N, Longitude 74°46'36.%"W. A Notice to Mariners (Appendix C) was issued on this item.—Concur

The position of the obstruction at the "CB" Buoy is correctly charted. RUDE and HECK divers obtained aleast depth of 47 feet, reduced for predicted tides, in lieu of the 43-foot charted least depth. Divers obtained a 56-foot general bottom depth around the obstruction, which agrees closely with 55 feet obtained the MT MITCHELL in 1980 (H9922).

The RUDE and HECK recommend that office review of this item be conducted in a timely manner so that the additional effective depth (47 feet VS 43 feet presently charted) can be charted. See the Evaluation Report

APPROVAL SHEET RH-20-08-83 RH-20-09-83

Field operations contributing to the accomplishment of this survey were conducted under my supervision with frequent personal checks of progress and adequacy. This report and field sheets have been closely reviewed. See Section G. for charting recommendations.


Russell C. Arnold LCDR, NOAA Commanding Officer NOAA Ships RUDE & HECK

FE-248 WD. OPR- D670 - RU/HE-83 JUNE ZO, 1983 YERSION SIGNALS/STATIONS CAPE HENRY LIGHT HOWE (NEW) Light List #152 LAT 365534.335V LON 760027.216 FILE NAVY LOOKOUT TOWER "C", 1976 Field Position LAT 365335.796 LON 755918.187 FILE CAVALLER HOTEL CUPOLA, 1929 ID MBR LAT 365208.381V LON 755902.012 FILE YIRGINIA BEACH MUNICIPAL TANK, 1953 ID MBR 4 LAT 365031.980/ LON 755923.523/ FILE . DAM NOCK MILLS NAVY TANK, 1953 ID NBR 5

LAT 364613.594 LON 755751.981

FILE

CHESAPEARE UGHT, 1966 Light hist # 151 ID MER LAT 365416.158 LON 754247.123 FILE BATTERY CRAMER, 1980 - Field Position ID MBR LAT 365504.201 LON 755944.491 ELEY'N 12.20 M FILE DAM NECK BOQ, 1981 Field Position ID NBR LAT 364717.522 LON 755734.990 ELEV'N 15.30 M CAPE HENRY LIGHT-HOWE (010), 1869 ID NER LAT 365532.330 LON 760030.516 FILE



A RICHAPPA

DIVING OPERATIONS

								-
Squipment	SINDAN	L subs	, prieum	10- 534	e, po	p-flas	+	
	eptn: <u>50</u>		,		•	:_60 N		
	-1	and the state of t	•	-				
1	IN	Out	Pressure	In Time	Out Time	Time	Depth	Com :
	Pressure	Pressure	2200 poi	1355	1404	9 min.	60 Ft.	
bn K	3000 ps/	νου μων		1407	1415	8 min.		
		80.0 ps,	2200 061	1423	1437	18 MIN		•
Mohan	3000 ps i	,000	2200	The Bo	for Time	as my N. 1	orh is	
<u> </u>					me den	A11 3	divens!	!
nish	3000 psi	360ps;	2760 ps;			i		
		/200 psi	1750 051	1447	1452	5 min	60 tt.	
musy	2950 psi	7200731		1455	1503	18 m/N		
(1447	1452	13 min. E		
ink	3000	1100 ps;	1900 ps 1	1447	 	1		1
i		:		,,,,,,				1
) •	•					
		;						
				<u> </u>	1	<u> </u>	J	
Post dive	comments:	The itel	n spoor	ned x	o be	A A	erge pl	ice of
rosc dive	, , ,	- /	et off	. 4	2 Use	t came	1. 604	M TI


RCA

ITEM INVESTIGATION

DATE: JUNE 20 1983	SHIP/LAUNCH LOUNCH 20
LOCATION: C- B- Boug Ch	espeake may south ENLHANCE
DIVE MASTER CORNSUSY	
	<u> </u>
DIVERS: CAMPAWAY	IN WATER
CHAK	NDEK WATER
COLLAND	ON SURVACE
Smith	IN BOAT
POST TION LLAST SEPTH TIME DEPTH 1. 1856 SO ft. 2. 1856 - 50 ft 3. SOTTOM TIME DEPTH GMT	TTEM
DRAWING OF ITEM	DESCRIPTION OF ITEM

The Hear was a large piece of metal wrecket; Livers were un able to my exceptly what is was. It are sandy bottom of 60 feet. He shout 51 feet.

Cankrupy's depth gave some a less depth at 57 feet work a max report of 59 feet. This gave is calibrated seconder to it needs.



APPEADIX C



U.S. DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration NOAA SHIPS RUDE & HECK 439 West York St. Norfolk, VA 23510

June 26, 1983

To:

Commander, 5th Coast Guard District

Federal Building 431 Crawford St. Portsmouth, VA 23705

From:

LCDR Russell C. Arnold

Commanding Officer

Subj: Notice to Mariners

Recent survey operations were conducted by the NOAA Ships RUDE and HECK in the vicinity of the wreckage of the MARINE ELECTRIC. Positions of the wreck and approximate least depth was determined with side scan sonar operations and fathometer searches. The wreck was subsequently hung by wire drag and later cleared to an effective depth of 65 feet, reduced for predicted tides. The position of the highest point of the wreck was:

Latitude: 37^o52'54.2"N Longitude: 74^o46'36.5"W

LORAN C: W - 15720.4

X - 26943.0

Y - 42037.7

Z - 59031.5

cc: AMC/MOA1 N/CG241 Note: The final position determined for the shoalest point during Evaluation and Analysis is Latitude 37°52' 54.0"
Longitude 74°46'36,3'
And the cleared effective depth by wire drag over the wreck is 64 feet.



AGGEGDIX E 10 Ex 69 _ALJ Ex__ "CERTIFIED TO 22 A TRUE COPY" For Id. Substitution authorized. 600-065°T **Bow Section** 500-400-300-FEET 230 200-Debris Stern Section 100-MARINE ELECTRIC 900 10 100 200 300 400 500 600 700 800 0 FEET

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY

TIDE NOTE FOR HYDROGRAPHIC SHEET

Processing Division: Atlantic Marine Center:

Hourly heights are approved for

. Tide Station Used (NOAA Form 77-12): 863-8863 Chesapeake Bay Bridge Tunnel, VA

Period: June 9-21, 1983

WIRE DRAG

WY DRIOUS RAYPHOOX SYMPECTY: OPR-D670 RU/HE-83 FE-248 WD (R/H-20-8-83)

OPR: D670

Locality: Offshore Chincoteague Inlet, VA

Plane of reference (mean lower low water): 24.84 feet

Height of Mean High Water above Plane of Reference is 2.7 feet

REMARKS: Recommended Zoning:

1. For item S/S Marine Electric apply - one hour time correction and x 1.37 range ratio.

Chief, Tidal Datums Section, Tides & Water Levels Branch DATE: 9/15/83

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY

TIDE NOTE FOR HYDROGRAPHIC SHEET

Processing Division: Atlantic Marine Center:

Hourly heights are approved for

Tide Station Used (NOAA Form 77-12): 863-8863 Chesapeake Bay Bridge Tunnel, VA.

June 20
Period: duly 12-21, 1983

WIRE DRAG:

OPR: D670

Locality: Offshore Chesapeake Bay entrance, Virginia

Plane of reference (mean lower low water): 24.84 feet

Height of Mean High Water above Plane of Reference is 2.7 feet

REMARKS: Recommended Zoning

1. For item #02940 and the corridor apply - 35 minute time correction and x1.34 range ratio.

Chief, Tidal Datums Section, Tides & Water Levels Branch

NOAA FORM 76-155 (11-72) No	ATIONAL	OCEANIC	U.S.	DEPARTM MOSPHER	ENT OF	COMMERC	E S	URVEY	IUMBER	
GEO	OGRAP							FE-248	WD	
Name on Survey	. / (on least	10. 01 10. 22	SURVEY D	A ANGLE A ORMA A ORMA E	ON LOCAL F	P.O GUI OF	AND WENT	Ly Light	List
,		. <u>/ B</u>	<u> </u>	<u> </u>	<u>/ E</u>	<u> </u>	G	<u>/ H</u>		
ASSATEAGUE ISLAND (tit)	Le) ✓	<u> </u>			1			· .	-	1
ATLANTIC OCEAN (title	/	-		_			ļ	-	 	2
CHESAPEAKE BAY (title)	/						ļ			3
VIRGINIA (title)	./						<u></u>			4
										5
										6
										7
			\ \ \							8
						 		<u> </u>		9
			 		 					+
				<u> </u>		+		 		10
		•								11
					-					12
										13
		-		•						14
·	·							ļ		15
:										16
										17
					Appro	oved:				18
					0					19
					, CX	ules'	+		in	20
					Chief	<u> </u>	pher - r	0 04%)	21
			-		n		1001			22
				 	7	Nov.	1984			-
										23
						,				24
	١.		1	· .		İ		[]		25

NOAA FORM 76-155 SUPERSEDES C&GS 197

HYDROGRAPHIC SURVEY STATISTICS REGISTRY NO.: FE-248WD

Number of positions		101
Number of soundings		0
Number of control stations		17
	TIME-HOURS	DATE COMPLETED
Preprocessing Examination Verification of Field Data	. 3	<u>Sept. 12, 1983</u>
Quality Control Checks		
Evaluation and Analysis	92	Nov. 16, 1984
Final Inspection	2	Nov. 16, 1984
TOTAL TIME	97	
Marine Center Approval		Nov. 16, 1984

Transmittal letter of survey and survey records will be included in the Descriptive Report to identify the records accompanying the survey.

ATLANTIC MARINE CENTER EVALUATION REPORT

REGISTRY NO.: FE-248WD FIELD NO.: R/H-20-8-83 and

R/H-20-9-83

Virginia, Atlantic Ocean, 26 Miles East of Assateague Island and Approaches to Chesapeake Bay

SURVEYED: June 9 through 21, 1983

<u>SCALE:</u> 1:20,000 <u>PROJECT NO.:</u> OPR-D670-RU/HE-83

SOUNDINGS: Wire Drag CONTROL: ARGO (Range-Range) and

Raytheon DE-719B fathometer Del Norte (Range-

Pneumofathometer Range)

Chief of Party......R. C. Arnold

.....T. G. Callahan

1. PURPOSE OF SURVEY

The purpose of this survey is adequately described in the Descriptive Report and in the Project Instructions. The results of this survey are discussed in this report and are portrayed on the smooth sheets (A&D) attached to this report.

2. CONTROL AND SHORELINE

a. The source of control was not adequately described in the Descriptive Report. Sections 6.e. and 6.f. of this report address this deficiency.

3. JUNCTIONS

There are no junctions on this survey.

4. COMPARISON WITH PRIOR SURVEYS

a. Hydrography

H-9922 (1980) 1:20,000

H-9099 (1969) 1:10,000

H-6595 (1940) 1:40,000

H-5355 (1933-34) 1:40,000

H-9922, H-9099, and H-6595 are prior hydrographic surveys which cover 100% of the common area of the present survey for AWOIS Item 02940, a Dangerous Submerged Obstruction at Latitude 36°51'18.7", Longitude 75°51'05.9". No conflicts exist between present clearance depths and prior hydrography. The obstruction located by the present survey was not found by any of the prior hydrographic surveys; however, the wire drag data from H-9871WD (1976) was brought forward on the smooth sheet of H-9922. See the comparison with survey H-9871WD (1976) below for discussion of this item.

H-5355 is a prior hydrographic survey which covers 100% of the common area of the present survey for the wreck S/S MARINE ELECTRIC at Latitude 37°52'54.0", Longitude 74°46'36.3". No conflicts exist between present clearance depths and prior hydrography. The hang, the wreck S/S MARINE ELECTRIC sank in February 1983.

b. Wire Drag

H-9871WD (1976) 1:20,000 H-6976WD (1945-47) 1:40,000

Prior wire drag survey H-9871WD covers 100% of the present survey area of AWOIS Item 02940, a <u>Dangerous Submerged Obstruction</u> at Latitude 36°51'18.7", Longitude 75°51'05.9". Clearance effective depths gained by the prior survey in the common area are greater than the clearance depths obtained by the present survey. The item hung at 45 feet and cleared by 44 feet on the prior survey is located only 27 meters north of the item hung on the present survey at 45 feet and not cleared. The present survey adequately proves the remained existence of the <u>dangerous submerged obstruction</u> and should be charted in accordance with the results and recommendations of survey H-9871WD (1976).

Prior wire drag survey H-6976WD covers 100% of the present survey area of AWOIS Item 02940, a <u>Dangerous Submerged Obstruction</u> at Latitude 36°51'18.7", Longitude 75°51'05.9", by an effective depth of 43 feet. No conflicts exist between present and prior data. No hangs or groundings existed on the prior survey within the common area.

5. COMPARISON WITH CHARTS

12211, 29th Edition, July 17, 1982 12221, 52nd Edition, August 21, 1982

a. Hydrography

Charted hydrography within the common areas originates with the previously discussed prior surveys and soundings from sources not readily ascertainable. The previously discussed prior surveys require no further consideration. Charting recommendations based on the results of this survey are:

1) AWOIS Item 02940 - <u>Dangerous Submerged Obstruction</u> at Latitude 36°51'18.7", Longitude 75°51'05.9" - first reported by Notice to Mariners No. 7 of 1944 was subsequently located and cleared by

H-9871WD (1976) and was verified by the present survey. The present survey hung the item in two directions with a shoalest hang depth of 45 feet but never cleared the obstruction. A pneumofathometer least depth was obtained but significantly conflicted with the hang data and the least depth was therefore rejected. It is recommended that this Dangerous Submerged Obstruction be charted in accordance with the results of H-9871WD (1976).

2) The S/S MARINE ELECTRIC - a collier more than 600 feet in length sank on February 12, 1983 at Latitude 37°52'54.0", Longitude 74°46'36.3". The shoalest point on the wreck was hung at an effective depth of 65 feet and was subsequently cleared in opposing directions by 64 feet. It is recommended that this wreck be charted as a Dangerous Sunken Wreck cleared by wire drag by an effective depth of 64 ft. at Latitude 37°52'54.0", Longitude 74°46'36.3".

b. Aids to Navigation

Two floating aids to navigation were common to the surveyed areas. The wreck buoy on the S/S MARINE ELECTRIC was not located. The Chesapeake Bay Entrance Lighted Whistle Buoy CB was located and agrees well with its charted position. Three fixed aids to navigation were used as control stations and are listed in the survey's control lists. All aids to navigation appear to serve their intended purposes. All fixed and floating aids noted in this survey except the wreck buoy on the S/S MARINE ELECTRIC are properly noted in the U.S. Coast Guard Light List, Volume I, 1983.

6. CONDITION OF SURVEY

The field sheets, field records, and reports are adequate and conform to the requirement of the <u>Wire Drag and Hydrographic Manuals</u> except:

a. All hydrography conducted in support of this survey is of reconnaissance value only as no sounding correctors were determined. However, the shoalest position found by fathometer search on the $\frac{S/S}{MARINE\ ELECTRIC}$ (Position 148 at Latitude 37°52'53.7", Longitude $\frac{74°46'36.9"}{36.9"}$) agrees extremely well (only 18 meters difference) with the hang position (Latitude 37°52'54.0", Longitude 74°46'36.3") of the shoalest point.

Awois

00318

- b. AWOIS Item 02940 a <u>Dangerous Submerged Obstruction</u> at Latitude 36°51'18.7", Longitude 75°51'05.9" was not cleared.
- c. No field A&D sheets or smooth composite draftings were generated by the field.
- d. The Descriptive Report is basically inadequate and incomplete. Chapters 5. of the <u>Wire Drag Manual</u> and the <u>Hydrographic Manual</u> specify the general requirements. Some of the items missing from the Descriptive Report are:

Survey Vessels
Control Stations
Signal Lists
Comparison with Charts
Comparison with Prior Surveys
Reference to Reports
Abstracts (Electronic Correctors, Statistics, Sonar Coverage,
Sonar Target, etc.)

- e. Apparently, the control stations used were not recovered as required by section 3.2.1. of the Project Instructions. The hydrographer makes no mention of station recovery or of recovery notes being submitted.
- f. Several station names in the signal list required correction to agree with the establishment records and all stations required the addition of the dates of station establishment. The signal list for this survey was not in the Descriptive Report but was found in the survey's accordian folder. The signal list has been corrected and is included in 'the Descriptive Report.
- g. Only two prior surveys (H-9922 and H-9871WD) of the seven prior surveys distributed to the field were included with the field records. No meaningful comparisons were made by the hydrographer.
- h. As stated in section 1.7 of the Project Instructions, comparisons and application of data was intended for charts 12211 and 12221. The hydrographer did not make comparisons with either of these charts.
- i. The Wire Drag Volumes lacked sufficient observational data to facilitate reliable positioning of hangs, particularly where a double hang has occurred.
- j. Additional annotations on the field plots, fathograms, sonargrams, Wire Drag Volumes, Sounding 'Volumes, and particularly the strip chart recordings would have been desirable.

7. COMPLIANCE WITH PROJECT INSTRUCTIONS

This wire drag field examination adequately complies with Project Instructions OPR-D670-RU/HE-83 except as noted in this report.

8. ADDITIONAL FIELD WORK

This is an adequate basic wire drag field examination for the S/S MARINE ELECTRIC and no additional work is recommended on this wreck. This survey is adequate for AWOIS Item 02940, a Dangerous Submerged Obstruction, only in conjunction with prior survey H-9871WD (1976); and in that consideration, no additional work on this obstruction is recommended.

9. MISCELLANEOUS

In strips containing a hang, the area past the initial contact on the hang was not claimed for effective depth coverage as the program of testing for lift is not considered sufficient to claim effective depths past the point of hang.

Maurice B. Hickson, III

Cartographer

Evaluation and Analysis

Inspection Report FE-248WD

The completed survey has been inspected with regard to survey coverage, investigation of hangs and clearance depths, cartographic symbolization, and verification or disproval of charted data. The survey complies with National Ocean Service requirements except as noted in the Evaluation Report. The survey records comply with NOS requirements except where noted in the Evaluation Report.

Inspected

R. D. Sanocki

Chief, Hydrographic Surveys

Processing Section

Hydrographic Surveys Branch

David B. MacFarland, Jr., LCDR, NOAA Chief, Hydrographic Surveys Branch

Approved November 16, 1984

Wesley V. Hull, RADM, NOAA

Director, Atlantic Marine Center



UNITED STATES DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

NATIONAL OCEAN SERVICE OFFICE OF CHARTING AND GEODETIC SERVICES ROCKVILLE, MARYLAND 20852

APR 5 1989 - - - - - Attack to

DR tor FE-148

RIA

MEMORANDUM FOR:

Commander Russell C. Arnold, NOAA

Chief, Hydrographic Surveys Branch

FROM:

Lieutenant Commander Maureen R. Kenny,

Chief, Operations Section

SUBJECT:


Charting Recommendation for Obstruction -


FE-248WD

A dangerous submerged obstruction (AWOIS item no. 2940), located in latitude 36°51'18.7"N, longitude 75°51'05.9"W, was investigated with a wire drag and a diver investigation during survey FE-248WD (1983). The hydrographer commented in his field notes that, although the obstruction was hung, a reliable clearance could not be obtained due to the erratic lifts and sags of the wire. The divers, however, stated they had excellent visibility and were able to describe and sketch the obstruction as well as obtain a least depth using the pneumatic depth gage. Because of the significant discrepancy between the hang depth and the divers' least depth, the evaluator recommended charting the obstruction according to the results of prior survey H-9871WD (1976).

After a reevaluation of the field data, a decision has been made to accept the diver investigation data, and recommend charting the obstruction with a least depth of 47 feet.







DEPARTMENT OF COMMERCE

National Oceanic and Atmospheric Administration National Ocean Survey Rockville, Maryland Hydrographic Index No. 69 K INDEX HYDROGRAPHIC SURVEYS Complete through August 1975 1961-1976 CAPE HENLOPEN - CAPE CHARLES DELAWARE-MARYLAND- VIRGINIA Depoter H-9578 H-9629 H-9759 H-9788 H-9640 H-9796 FE-248WD Diagram No. 1220-2 & 1222-4 HYDROGRAPHIC SURVEYS 10.000 10.000 20.000 20.000 10.000 20.000 10.000 20.000 H-9629 H-9639 H-9640 F.E. No. 1, 1971 On Scales of 1 10000 6 34 inches = 1 statute mile 1 20000 3 17 inches = 1 statute mile

FE-248WD

△-Wire drag

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. FE-248WD

INSTRUCTIONS

- A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

 1. Letter all information.

 2. In "Remarks" column cross out words that do not apply.

 3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Revi

CHART	DATE	CARTOGRAPHER	REMARKS
1222	5-12-85	H. Rodden	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 82 No corr retained as charted
12211	2-11-86	R. Suft	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 45 FULLY APPLIED
12207	2-11-86	R. Tests	Full Para Briese After Verification Review Inspection Signed Via
			Drawing No. 25 NO CORR, RETAINED AS CHARTED
12220	2-11-86	R. Tacks	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 52 NO CORP, RETAINED AS CHINETED
12200	2-11-86	R. Buhr	Full Past Before After Verification Review Inspection Signed Via
			Drawing No. 50 FULLY APPLIED
13003	2-11-86	R. But	Full Part Defore After Verification Review Inspection Signed Via
			and revised "10 3" to 102"
12208	uliala	J. Robinson	and revised 104 to 102
12000	11/19/91	J. POBINSON	Full Raft Before After Venification Review Inspection Signed Via
			Drawing No. 11 Reunstraction
			- See also later date H-10337 dated 1990
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.